

ASAP

Dart Aerospace Ltd.

Date: Monday, 21/07/2008 10:53:27 AM  
User: Julie Lecocq

## Process Sheet

Customer	: CU-DAR001 Dart Helicopters Services	Drawing Name	: STRUT
Job Number	: 40682	Part Number	: D2565307
Estimate Number	: 10981	Drawing Number	: D2565 REV E
P.O. Number	:	Project Number	: N/A
This Issue	: 21/07/2008 S.O. No. :	Drawing Revision	: E
Prsht Rev.	: NC	Material	:
First Issue	: / / Type : SMALL / MED FAB	Due Date	: 10/08/2008 Qty: 5 Um: Each
Previous Run	: 26642		
Written By	:		
Checked & Approved By	: <u>JUL 08.7.21</u>		
Comment	: Est:A 02.06.10 New Issue NG		

## Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0	M304TR0750W049	304 RD Tube .750 x .049W
-----	----------------	--------------------------



Comment: Qty.: 1.8462 f(s)/Unit Total : 9.2311 f(s)  
Material: 304/316 SS tubing 0.750" Dia. x 0.049" wall  
(M304TR0750W049) Batch No: M108846

SB 08/08/20 (5)

2.0	BRAKE NC	NC BRAKE
-----	----------	----------



Comment: BRAKE NC  
Punch as per Dwg D2565 using DT 8313

PTU →

3.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
-----	-------------	-------------------------------



Comment: SMALL & MEDIUM FAB RESOURCE 1  
Deburr

SB 08/08/26 (5) Hm

4.0	QC5	INSPECT WORK TO CURRENT STEP
-----	-----	------------------------------



Comment: INSPECT WORK TO CURRENT STEP

SB 08/08/29 (5)

5.0	POWDER COATING	POWDER COATING
-----	----------------	----------------



Comment: POWDER COATING  
Powder Coat White (Ref: 4.3.5.2) as per QSI 005 4.3

(5X)

START TIME:

OVEN TEMPERATURE:

FINISH TIME:

1:50  
4:20  
2:20

M. 08/09/08

Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: D2565-307 PAR #: W/A Fault Category: Prod / Ins' med & Small NCR: Yes No DQA: D Date: 08/09/05  
D205-638 QA: N/C Closed: D Date: 08/09/05

NCR: 40682		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			
03.03.27	2	Dimension 20.06 is out of tolerance (ALL 5 parts) Root Cause: Tape measure used for mts. is <del>out of tolerance</del>	PH 03.03.27 05/042	- Recommend to cutoff <del>one</del> 1 end and reuse part on shorter strut - Destroy tape measure	JS 08/08/28	S 08/08/29	PH 03.09.02 053042	S 08/08/27
		not reading correctly. It has two small kinks: employee was measuring w/ the 10" line		that is out of tolerance D2565-109 B 411605 used on.				

NOTE: Date & initial all entries

Date: Monday, 21/07/2008 10:53:27 AM  
User: Julie Lecocq

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: STRUT

Job Number: 40682

Part Number: D2565307

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



JS



Comment: INSPECT POWDER COAT

08-09-02

(KS)

7.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: ST 253

JS

08/09/02 (KS)

8.0

QC21

FINAL INSPECTION/W/O RELEASE



08/09/03 JS

Comment: FINAL INSPECTION/W/O RELEASE

Job Completion



MF 08-09-03

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_


NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries



DESIGN	DRAWN BY	<b>DART AEROSPACE LTD</b> HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D2565	REV. E SHEET 1 OF 1
DATE 04.05.05		TITLE STRUT	SCALE 1:3
A	96.05.03	NEW ISSUE	
B	97.03.15	CORRECT D2565-111 DIM. A	
C	98.10.05	UPDATED MATERIAL NOTE (TSR A603)	
D	02.06.05	ADD -3XX PARTS; ADD FINISH	
E	04.05.05	ADD D2565-401-411; RMV ANGLE D	

RELEASED  
04.05.05



PART #	A	B	DIA C
D2565-101	20.52	19.72	0.316
D2565-103	18.21	17.41	0.316
D2565-105	20.19	19.39	0.316
D2565-107	13.43	12.63	-
D2565-109	12.31	11.51	-
D2565-111	13.65	12.85	-
D2565-201	22.79	22.00	0.316
D2565-203	20.75	19.95	0.316
D2565-205	21.22	20.42	0.316
D2565-207	16.07	15.27	-
D2565-209	15.16	14.36	-
D2565-211	14.14	13.34	-
D2565-301	27.03	26.23	0.316
D2565-303	25.34	24.54	0.316
D2565-305	23.73	22.93	0.316
D2565-307	20.86	20.06	-
D2565-309	20.17	19.37	-
D2565-311	16.30	15.50	-
D2565-401	18.29	17.49	0.316
D2565-403	15.64	14.84	0.316
D2565-405	19.45	18.65	0.316
D2565-407	10.79	9.99	-
D2565-409	9.34	8.54	-
D2565-411	13.81	13.01	-

#### GENERAL NOTES

- 1) MATERIAL: AISI 304/316/318 SS 0.750 OD X 0.049 WALL  
(REF DART SPEC. M304TR0.750W0.049)  
ENSURE SEAMLESS TUBE IS USED
- 2) FINISH: POWDER COAT WHITE (4.3.5.2) PER DART QSI 005 4.3
- 3) TOLERANCES PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES

20.196

SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 40682

Copyright © 1996 by DART AEROSPACE LTD


THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



DESIGN KE	DRAWN BY KE	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED DMJ	APPROVED KE	DRAWING NO. D2638	REV. A SHEET 1 OF 1
DATE 98.04.28		TITLE PUNCH DT8117 SPEC CONTROL	SCALE 1:1
A	98.04.28	NEW ISSUE	

RELEASED  
98/05/05 KE

SPECIFICATION CONTROL DRAWING  
FOR PUNCH DT8117



SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 40682